Estimate

FROM

Business name _____

Phone _____

Email _____

Address _____

License no. _____

Estimate no. _____

Date _____

Valid until _____

BILL TO

Client name _____

Address _____

Job address _____

Phone _____

Email _____

Description	Qty	Unit price	Amount
Demo and haul existing slab, 4 in. (sq ft)	400	$3.50	$1,400.00
Grade and compact 4 in. gravel base (sq ft)	400	$1.75	$700.00
Forms, three sides (linear ft)	60	$3.00	$180.00
#3 rebar, 18 in. on center, with chairs (sq ft)	400	$1.25	$500.00
Ready-mix, 4,000 psi, delivered (cu yd)	5.5	$185.00	$1,017.50
Place, broom finish, tool control joints (sq ft)	400	$4.25	$1,700.00
Short-load fee (under 8-yard minimum)	1	$250.00	$250.00
Penetrating sealer, 1 coat (sq ft)	400	$0.75	$300.00

NOTES AND TERMS

Valid 14 days. No pour in rain or below 40F. No cars for 7 days. Hairline cracks under 1/8 in. are normal. Bad subgrade billed per cu yd.

Subtotal $6,047.50

Discount _____

Tax (____%) _____

Total _____

Accepted by _____

Date _____

Signature _____

Free estimate template from makemyestimate.com. Fill it in online with automatic totals at https://makemyestimate.com/