Estimate

FROM

Business name

Phone

Email

Address

License no.

Estimate no.

Date

Valid until

BILL TO

Client name

Address

Job address

Phone

Email

Description	Qty	Unit price	Amount
Remove and dispose carpet, pad, tack strip (sq ft)	620	$1.25	$775.00
Self-leveling compound, low areas (sq ft)	120	$2.50	$300.00
LVP, 20 mil wear layer, incl. 10% waste (sq ft)	682	$3.40	$2,318.80
LVP installation labor (sq ft)	620	$2.75	$1,705.00
Quarter round, primed, installed (linear ft)	210	$3.00	$630.00
Transition strips	3	$45.00	$135.00
Move and replace furniture (per room)	3	$50.00	$150.00
LVP stair treads and risers with nose (per step)	13	$110.00	$1,430.00

NOTES AND TERMS

Valid 30 days. Deposit to order material, balance on completion. Damaged subfloor $95 per 4x8 sheet; extra leveling $2.50/sq ft, approved first.

Subtotal	$7,443.80
Discount	
Tax (____%)	
Total	

Accepted by

Date

Signature

Free estimate template from makemyestimate.com. Fill it in online with automatic totals at https://makemyestimate.com/