Estimate

FROM

Business name

Phone

Email

Address

License no.

Estimate no.

Date

Valid until

BILL TO

Client name

Address

Job address

Phone

Email

Description	Qty	Unit price	Amount
3-ton condenser, 15.2 SEER2	1	$4,600.00	$4,600.00
Gas furnace, 80,000 BTU, 96% AFUE	1	$3,900.00	$3,900.00
Cased evaporator coil, 3-ton	1	$1,450.00	$1,450.00
Refrigerant line set, 3/8 x 3/4 in (linear ft)	30	$28.00	$840.00
Insulated supply duct, 8 in (linear ft)	40	$22.00	$880.00
Programmable thermostat, installed	1	$275.00	$275.00
Install labor, 2-person crew (hours)	16	$135.00	$2,160.00
Permit and inspection	1	$250.00	$250.00

NOTES AND TERMS

Equipment pricing valid 21 days. Deposit to order equipment, balance at start-up. Mfr parts warranty (register in 60 days) plus labor warranty. Panel upgrades excluded.

Subtotal $14,355.00

Discount

Tax (____%)

Total

Accepted by

Date

Signature

Free estimate template from makemyestimate.com. Fill it in online with automatic totals at https://makemyestimate.com/